Finnish-German BIM-Workshop 5.9.2023

Shaping the Future of the Built Environment through BIM and Digital Twins



Scheduling cases Destia Finland and WSB Frontage Road USA

Jouni Ojala, Director 4D Planning, Granlund Oy






Kalasatamasta pasilaan project

- Light rail, roads, pedestrian ways
 - 4,5 km
 - 6-8 meters wide
- Budget 80 M€
- Alliance project
- Granlund's client: Destia
- 1st Infra4D client project for Granlund












Frontage Road


- Simple Road project to work as a business card
- Granlund's role: bring 4D to digital twin delivery
- Granlund's client: WSB Engineering





	20000000		Name	Duration	Start		May	Jul		Oct	JUCT		Jan 2024		Apr			Jul			Oct			Jan 2025	2025		
	ID	Area					wk 19 w	Jul Aug	Sep		Nov	Dec		Feb	Mar		May	Jun		Aug	Sep		Nov	Dec		Feb	Mar
0 2								wk 27 wk 32	wk 36	wk 40	wk 45	wk 49	wk 1	wk6	wk 10	wk 14	wk 19	wk 23	wk 27	wk 32	wk 36	wk 41	wk 45	wk 49	wk 2	wk6	wk '
			Schedule.G4D	2d, 1h, 56m	12.06.23			Schedule.G4D																			
			Area.US 278 to Dennis Creek	2d, 1h, 56m	12.06.23	14.06.23		Area US 278 to Dennis Ci	eek																		
			Station.100+00.00	3h, 32m	12.06.23	12.06.23		Station.100+00.00																			
			Work type.CONCRETE/STRUCTURES	3h, 32m	12.06.23	12.06.23		Work type.CONCRETE/ST	RUCTURES																		
160 \$	T00960	US 278 to Dennis Creek	100+00.00 - Install Curb & Gutter - Frontage Rd	3h, 32m	12.06.23 (*)	12.06.23 (*)		100+00.00 - Install Curb &	Gutter - Fron	ntage Rd.																	
			Station.103+00.00	4h, 48m	12.06.23	13.06.23		Station.103+00.00																			
			Work type.CONCRETE/STRUCTURES	4h, 48m	12.06.23	13.06.23		Work type CONCRETE/S	RUCTURES	3																	
176 S	T00976	US 278 to Dennis Creek	103+00.00 - Install Curb & Gutter - Frontage Rd	4h, 48m	12.06.23	13.06.23		103+00.00 - Install Curb &	Gutter - Fro	ntage Rd.																	
			Station.106+00.00	4h, 48m	13.06.23	13.06.23		Station.106+00.00																			
			Work type.CONCRETE/STRUCTURES	4h, 48m	13.06.23	13.06.23		Work type.CONCRETE/S	FRUCTURES	3																	
193	T00992	US 278 to Dennis Creek	106+00.00 - Install Curb & Gutter - Frontage Rd	4h, 48m	13.06.23	13.06.23		106+00.00 - Install Curb &	Gutter - Fro	ntage Rd.																	
			Station.109+00.00	4h, 48m	13.06.23	14.06.23		Station.109+00.00																			
			Work type.CONCRETE/STRUCTURES	4h, 48m	13.06.23	14.06.23		Work type CONCRETE/S	TRUCTURES	3																	
210	T01008	US 278 to Dennis Creek	109+00.00 - Install Curb & Gutter - Frontage Rd	4h, 48m	13.06.23	14.06.23		109+00.00 - Install Curb 8	Gutter - Fro	ntage Rd.																	

5.9.2023 © Granlund |



5.9.2023

Lessons learned





Standardization of data

- Non-IFC, non-standard data
 - A lot of effort to make models usable

- Remedies
 - Collaborate with designers have them publish usable files (IFCs)
 - Work towards standardized practices within the industry
 - In Finnish building construction IFCs are routinely published



Right bite size

- From 3x3 meter grid to
- Whole 100 yards
- Due to using app to report completions



55

What you measure is what you get

- Schedule as a daily tool to drive production
- Having an accurate schedule changes the game
 - and the way site people need to relate to it
 - Know what you need to do today
 - Report progress
 - Or obstacles
 - ...be able to succeed every day!
- Philosophy and position of the schedule needs to be real life daily tool to know and report schedule



International collaboration is possible

- We are able to work with companies in other countries
- Challenges in construction industry seem to be surprisingly similar between countries
- Local champion is needed



Contact information

Jouni Ojala

Director, 4D Planning puh. +358 40 071 7454 jouni.ojala@granlund.fi



Granlund Oy | Malminkaari 21, PL 59, 00701 Helsinki

